PROJECT LOCATION

LOCATION MAP SCALE: 1" = 500'

LEGEND: STANDARD CONVENTIONS North Arrow W/No. Coor. Grid Arrow O Iron Pin (Found) **≖** Sign Edge Of Road Limit Of Marsh S Sewer Manhole Stone Wall Concrete Pavement © Electric Manhole Ledge Outcrop Dirt Road Telephone Manhole B.C.L.C. Inland Wetland Limits "C" Catch Basin Concrete Curb "C-L" Catch Basin STATE LINE Guide Rail Light Pole Concrete Median Barrier Power Line Metal/Timber Post Bit. Walk Swamp - Utility Pole Conc. Sidewalk Building d Guy Anchor Railroad Tracks Transmission Tower $|\times|$ ⊗ Water Gate Riprap Chain Link Fence ^{GV} Gas Valve Hedge Row xxxxxxxx Rustiç Fence © Gas Meter Tree Line W Pipe Fence Shrub 💥 ── Mail Box Evergreën Tree 🌣 _____ X ____ Fence Line Board Fence Deciduous Tree 👸 Guide Rail Water Edge Retaining Wall Piping (Sanitary) Highway Line _____ D____ Piping (Storm) Stream Street Line Ditch ——— E——— U/G Elec. Line Property Line ------ W ------ Water Line TOWN LINE Lot Line ----OHW----- Overhead Utilities Boring Location 🕜 Easement Line —— ⊤ — U/G Tele. Line


TOWN OF NEW MILFORD CONNECTICUT

PLANS FOR THE NEW PUBLIC WORKS FACILITY

TO BE MAINTAINED BY THE TOWN OF NEW MILFORD (FOR PERMITTING ONLY)



LIST OF DRAWINGS		
SHEET NO.	TITLE	
1	TITLE SHEET	
	SITE SURVEY (SEPARATE PLAN SHEET)	
2	EXISTING CONDITIONS / INDEX PLAN	
3	PROPOSED OVERALL DEVELOPMENT PLAN	
4 - 6	EROSION CONTROL PLAN	
7	SITE DRAINAGE DETAILS	
8	EROSION CONTROL DETAILS	



TECHNICAL SPECIFICATIONS: STATE OF CONNECTICUT DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR ROADS, BRIDGES AND INCIDENTAL CONSTRUCTION (FORM 818) AND ALL LATEST SUPPLEMENTAL SPECIFICATIONS THERETO, AS WELL AS THE TOWN OF NEW MILFORD PUBLIC IMPROVEMENT SPECIFICATIONS.

DESIGN STANDARDS: AASHTO POLICY ON THE GEOMETRIC DESIGN OF HIGHWAYS AND STREETS, DATED 2004 AND THE CONNECTICUT DEPARTMENT OF TRANSPORTATION HIGHWAY DESIGN MANUAL DATED 2003.

SURVEY: ALL COORDINATES ON THE PROJECT ARE BASED ON NAD 83. ALL ELEVATIONS ARE BASED ON NAVD 1988.


CONNECTICUT DEPARTMENT OF TRANSPORTATION OR TOWN OF NEW MILFORD BIDDING AND OTHER INFORMATION AND DOCUMENTS WHICH ARE OBTAINED THROUGH THE INTERNET, WORLD WIDE WEB SITES OR OTHER SOURCES ARE NOT TO BE CONSTRUED TO BE OFFICIAL INFORMATION FOR THE PURPOSES OF BIDDING OR CONDUCTING OTHER BUSINESS WITH THE TOWN OF NEW MILFORD.


IT IS THE RESPONSIBILITY OF EACH BIDDER AND ALL OTHER


INTERESTED PARTIES TO OBTAIN ALL BIDDING RELATED INFORMATION
AND DOCUMENTS FROM OFFICIAL SOURCES WITHIN THE TOWN OF


PERSONS AND/OR ENTITIES WHICH REPRODUCE AND/OR MAKE SUCH INFORMATION AVAILABLE BY ANY MEANS ARE NOT AUTHORIZED BY THE TOWN OF NEW MILFORD TO DO SO AND MAY BE LIABLE FOR CLAIMS RESULTING FROM THE DISSEMINATION OF UNOFFICIAL, INCOMPLETE AND/OR INACCURATE INFORMATION.


DESIGNED BY WMC CONSULTING ENGINEERS			
SUBMITTED BY	DATE		
PUBLIC WORKS DIRECTOR - TOWN OF NEW MILFORD			
JACK HEALY	DATE		

















GENERAL

THIS PLAN PROPOSES EROSION CONTROL MEASURES TO HELP CONTROL ACCELERATED EROSION AND SEDIMENTATION AND REDUCE THE DANGER FROM STORM WATER RUNOFF AT THE SITE. THE RUNOFF SHALL BE CONTROLLED BY THE INTERCEPTION, DIVERSION, AND SAFE DISPOSAL OF PRECIPITATION. RUNOFF SHALL ALSO BE CONTROLLED BY STAGING CONSTRUCTION ACTIVITY AND PRESERVING NATURAL VEGETATION WHENEVER POSSIBLE. EXISTING VEGETATION SHALL BE PROTECTED AND ONLY THAT CLEARING AND GRUBBING ABSOLUTELY NECESSARY FOR THE PROPOSED CONSTRUCTION SHALL BE PERFORMED. ALL DISTURBED AREAS SHALL BE RESTORED TO THEIR ORIGINAL CONDITION AND CONTOUR, UNLESS OTHERWISE INDICATED ON THE PLANS. THE CONTRACTOR SHALL TAKE SPECIAL CARE WITH HIS CONSTRUCTION METHODS AND SHALL COMPLY WITH THE FOLLOWING GUIDELINES. REFERENCE IS MADE TO THE "CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENTATION CONTROL" (2002), AS AMENDED. THE GUIDELINES ARE OBTAINABLE FROM THE CONNECTICUT DEPARTMENT OF ENERGY AND ENVIRONMENTAL PROTECTION, 79 ELM STREET, HARTFORD, CONNECTICUT 06106, AND SHOULD BE USED AS A REFERENCE IN CONSTRUCTING THE EROSION AND SEDIMENTATION CONTROLS INDICATED ON THESE PLANS.

EROSION CONTROL

ALL AREAS SHALL BE PROTECTED FROM EROSION DURING AND AFTER CONSTRUCTION, PARTICULARLY THE STORAGE OF EXCAVATED OR STOCKPILED MATERIAL. THE CONTRACTOR SHALL CAREFULLY STRIP ALL TOPSOIL, LOAM, OR ORGANIC MATTER PRIOR TO TRENCHING OR OTHER OPERATIONS AND SHALL STORE THEM SEPARATELY FROM ALL OTHER MATERIALS DURING EXCAVATION. EACH STOCKPILE MUST BE ADEQUATELY RINGED WITH SEDIMENTATION CONTROL SYSTEM (I.E. HAY BALES AND/OR GEOTEXTILE FENCE). DEBRIS AND OTHER WASTE RESULTING FROM EQUIPMENT MAINTENANCE AND CONSTRUCTION WILL NOT BE DISCARDED ON SITE. STABILIZING OF SLOPES SHALL BE DONE IMMEDIATELY AFTER CONSTRUCTION OF SLOPES. SLOPES STEEPER THAN 3:1 SHALL BE PROTECTED WITH EROSION CONTROL MATTING. THIS MATTING IS MANUFACTURED COMBINATIONS OF MULCH AND NETTING AND SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS. ALL OTHER AREAS SHALL BE MULCHED WITH HAY OR STRAW AT A RATE OF 2 TO 3 TONS PER ACRE. STRAW OR HAY MULCH MUST BE ANCHORED IMMEDIATELY AFTER SPREADING TO PREVENT WINDBLOWING. THE METHODS RECOMMENDED BY THE "CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENTATION CONTROL" SHALL BE USED FOR THE ANCHORING OF MULCH OR NETTING.

EROSION AND SEDIMENTATION CONTROL PLAN

AN EROSION AND SEDIMENTATION CONTROL PLAN MUST BE SUBMITTED IN WRITING TO THE ENGINEER AND APPROVED BY THE ENGINEER PRIOR TO THE COMMENCEMENT OF ANY CONSTRUCTION ACTIVITIES.

SEDIMENTATION CONTROL SYSTEM - THE SEDIMENTATION CONTROL SYSTEM SHALL CONSIST OF A GEOTEXTILE BARRIER FENCE. THE SEDIMENTATION CONTROL SYSTEM SHALL BE INSTALLED IMMEDIATELY AFTER A CUT SLOPE HAS BEEN GRADED, BEFORE A FILL SLOPE HAS BEEN CREATED AND AS INDICATED ON THE PLANS. THE SYSTEM IS DESIGNED TO INTERCEPT SILT AND SEDIMENT BEFORE IT REACHES THE WETLANDS OR WATERCOURSES. DEPOSITS OF SEDIMENT AND SILT ARE TO BE PERIODICALLY REMOVED FROM THE UPSTREAM SIDE OF THE FENCE. THIS MATERIAL IS TO BE SPREAD AND STABILIZED IN AREAS NOT SUBJECT TO EROSION, OR IN AREAS WHICH ARE NOT TO BE PAVED OR BUILT ON. THE SEDIMENTATION CONTROL SYSTEM IS TO BE REPLACED AS NECESSARY TO PROVIDE PROPER FILTERING ACTION. THE SYSTEM IS TO REMAIN IN PLACE AND BE MAINTAINED TO INSURE EFFICIENT SILTATION CONTROL UNTIL ALL AREAS ABOVE THE FENCE ARE STABILIZED AND VEGETATION HAS BEEN ESTABLISHED.

STACKED HAY BALES - HAY OR STRAW BALES USED FOR EROSION CONTROL SHALL BE STACKED AT CATCH BASINS WHERE SEDIMENT MAY ENTER THE CATCH BASIN OR AS DIRECTED BY THE ENGINEER. DEPOSITS OF SEDIMENT AND SILT ARE TO BE PERIODICALLY REMOVED FROM THE UPSTREAM SIDE OF THE EROSION CHECKS. THIS MATERIAL IS TO BE SPREAD AND STABILIZED IN AREAS NOT SUBJECT TO EROSION, OR IN AREAS WHICH ARE NOT TO BE PAVED OR BUILT ON. HAY OR STRAW BALES ARE TO BE REPLACED AS NECESSARY TO PROVIDE PROPER FILTERING ACTION. THE SYSTEM IS TO REMAIN IN PLACE AND BE MAINTAINED TO INSURE EFFICIENT SILTATION CONTROL UNTIL ALL AREAS ABOVE THE EROSION CHECKS ARE STABILIZED AND VEGETATION HAS BEEN ESTABLISHED.

IN ALL AREAS, REMOVAL OF TREES, BUSHES, AND OTHER VEGETATION, AND DISTURBANCE OF THE SOIL, IS TO BE KEPT TO AN ABSOLUTE MINIMUM WHILE ALLOWING PROPER DEVELOPMENT OF THE SITE.

DURING CONSTRUCTION, AS SMALL AN AREA OF SOIL AS POSSIBLE SHOULD BE EXPOSED FOR AS SHORT A TIME AS POSSIBLE. AFTER CONSTRUCTION, GRADE, RESPREAD TOPSOIL, AND STABILIZE SOIL BY SEEDING AND MULCHING AS TO PREVENT EROSION.

EROSION AND SEDIMENTATION CONTROL MAINTENANCE PROCEDURES

ALL EROSION AND SEDIMENTATION CONTROL DEVICES SHALL BE INSPECTED DURING CONSTRUCTION ON A DAILY BASIS AND FOLLOWING ALL STORMS BY THE RESIDENT ENGINEER. THE CONTRACTOR SHALL MAINTAIN AND MAKE REPAIRS AND REMOVE SEDIMENT AS REQUESTED BY THE ENGINEER. THIS WORK SHALL BE PERFORMED WITHIN 24 HOURS OF THE REQUEST AND THERE SHALL BE NO SEPARATE PAYMENT FOR THIS WORK.

THE CONTRACTOR SHALL CLEAN SEDIMENT AND DEBRIS FROM ALL DRAINAGE STRUCTURES, AND PIPES AT THE COMPLETION OF CONSTRUCTION, AND AS REQUESTED BY THE ENGINEER TO KEEP THE SYSTEM FUNCTIONING PROPERLY DURING CONSTRUCTION.

FOLLOWING COMPLETION OF CONSTRUCTION, THE CONTRACTOR SHALL REPAIR ALL ERODED AREAS AND ENSURE A GOOD STAND OF TURF IS ESTABLISHED THROUGHOUT. THE CONTRACTOR SHALL REPAIR ALL ERODED OR DISPLACED RIPRAP, AND CLEAN SEDIMENT COVERED STONES.

ALL APPROPRIATE EROSION AND SEDIMENT CONTROL MEASURES SHOULD BE ESTABLISHED PRIOR TO AND BE MAINTAINED THROUGH ALL CONSTRUCTION PHASES.

WETLAND IMPACTS & DISTURBANCE

WETLAND DISTURBANCE: NO DIRECT WETLAND IMPACTS ARE PROPOSED FOR THIS PROJECT,

WETLAND FRINGE AREA RESTORATION: ALL DISTURBED WETLAND FRINGE AREAS SHALL BE RESTORED WITH A WETLAND SEED MIX OR WETLAND TRANSITIONAL SEED MIX CONTAINING ONLY SPECIES NATIVE TO CONNECTICUT. ALL SEED MIX FOR WETLAND OR WETLAND FRINGE (TRANSITIONAL) AREAS MUST BE SUBMITTED AND APPROVED IN ADVANCE. THIS WORK SHALL NOT BE PAID SEPARATELY, BUT SHALL BE INCLUDED IN THE GENERAL COST OF OTHER RELATED WORK ITEMS.

• WENGELL, McDONNELL & COSTELLO • CHECKED S.R.M. 87 HOLMES ROAD DESCRIPTION NEWINGTON, CT 06111

03/11/24

REVISIONS

PREPARED FOR

TOWN OF NEW MILFORD

10 MAIN ST

NEW MILFORD, CT 06776

(860) 667-9624

EROSION CONTROL NOTES NEW PUBLIC WORKS FACILITY NEW MILFORD, CONNECTICUT

SHEET _ NM_DPW_PD_ 23057.10 _ DPW Facility REV. SIZE PROJECT FILE NAME NUMBER OF